

**SURVEY &
REMONUMENTATION**

FEB 18 1994

COMMISSION

REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ionia</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>5W</u>	<u>C-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
 93 DEC 27 P 1:11
 STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marinus Mulder, in a field survey on September 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by Lucious Lyon, U.S. Deputy Surveyor in 1826. He set a wood post witnessed by a 36" Lynn S 21° W 28 links and a 15" Beech S 78½° E 71 links.
PERPETUATION: D.C. Crawford former Ionia County Surveyor has a marginal witness note for C-1 in the County Surveyors copy of the G.L.O. notes. He states: 1890 8" Maple N 83° W 284 links and 8" Cherry S 6° W 182½ links. I, Marinus Mulder, found the corner Crawford set in September of 1982 and the information is recorded in Liber 2 page 230. Crawford was noted for setting solid 2 1/4" clay cylinders.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rod and cap next to 2 1/4" clay cylinder with stones at the base. Removed 5/8" rod and cap and replaced with a 3/4" rod 24" long with a 2 3/4" diameter cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 24" steel rod with a 2 3/4" diameter cap stating "Ionia County P.S. 25863" with the following witnesses:
 Southwest corner 12" x 12" concrete anchor post N 46° E 42.24'
 Nail & tag West side 6" Maple N 61° E 50.88'
 Nail & tag North side power pole S 64° E 82.76'
 Nail & tag Northeast side telephone pole S 34° E 82.07'

Signed by Marinus Mulder Date October 26, 1993
 Surveyor's Michigan License No. 25863