

**SURVEY &
REMONUMENTATION**

FEB 18 1994

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia
(County)

Located In:

Corner Code =#

- | | | | | | |
|------------------------------------|---|-----------|---|-----------|------------|
| 1. Public Land Survey | T | <u>5N</u> | R | <u>5W</u> | <u>C-2</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Deane M. Robinson
REGISTER OF DEEDS

93 DEQ 27 P 1:13

STATE OF MICHIGAN
IONIA COUNTY
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on September 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	•	5	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
Original corner set by U.S. Deputy Surveyor, Lucious Lyon in 1826. He set a wood post witnessed by a 7" Sugar S 79° E 14 links and a 17" Sugar S 35° W 30 links.
PERPETUATION: D.C. Crawford former Ionia County Surveyor has a marginal witness note for C-2 in the county surveyors copy of the G.L.O. notes. He states: 1890 3" Elm N 68½° E 103 links & 10" White Oak S 31° E 101 links. Crawford was noted for setting solid 2 1/4" clay cylinders. I, Marinus Mulder, found the corner Crawford set in September of 1982 and the information is recorded in Liber 2 page 230.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 5/8" rod and cap next to 2 1/4" clay cylinder with stones at base. Replaced 5/8" rod with 3/4" rod and cap. This is accepted as a perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 3/4" x 36" steel rod with a 2 3/4" cap next to clay cylinder stating "Ionia County P.S. 25863" with the following witnesses:
Nail & tag Northeast side 5" wood post N 58° W 15.30'
Nail & tag South side 3" Oak clump S 85° W 20.23'
Nail & tag East side 3" Oak clump S 47° W 30.43'
Nail & tag West side power pole N 45° E 74.94'

Signed by *marinus mulder* Date October 26, 1993
Surveyor's Michigan License No. 25863