

1993

REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia (County) Located In: Corner Code ##

1. Public Land Survey T 5 N R 5 W D-11  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Oliver M. O'Brien  
REGISTER OF DEEDS

93 SEP 21 P 3:24

STATE OF MICHIGAN  
IONIA COUNTY  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	15		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on August 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by Lucious Lyon, U.S. Deputy Surveyor in 1827. Set wood post witnessed by (1) 10" White Oak N 63° E 4 links (2) 33" Red Oak S 25° E 20 links.  
 Perpetuation: Thomas Cornell former Ionia County Surveyor performed a sectional survey in Section 29 on November 9-12 1874. This is recorded in Volume 1 page 70 Ionia County Surveyors Books. He state "Large stone with crocker around". On December 9 of 1887 D.C. Crawford former Ionia County Surveyor performed more work in Section 29 recorded in Volume 1 page 418 of the Ionia County Surveyors Books. He makes no specific description of the corner. Crawford has marginal witness notes on the County Surveyors copy of the G.L.O. notes found in the "Big Red Book". He state "1891 - (1) 8" Maple S 7° W 51 1/2 links (2) 3" Elm N 75° E 156 links."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No 1891 witness trees remain. Excavated roadbed and 12" below gravel surface found 2 1/4" clay cylinder with stones around it. Accepted as a careful & faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 36" steel bar next to cylinder with 2 3/4" diameter cap staving. "Ionia County P.S. 25863".

Witnesses:

- Nail & tag East side 22" Walnut N 42° W 42.75'
- Nail & tag Northwest side 12" Cherry S 64° W 38.56'
- Nail & tag East side 18" Twin Ash S 34° W 29.49'
- Nail & tag South side 20" Twin Walnut N 80° E 96.30'

LIBER 003 PAGE 35

Signed by marinus mulder

Date September 8, 1993

Surveyor's Michigan License No. 25863