

DEC 07 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 215

COMMISSION

For corners in

IONIA (County)

Located In:

Corner Code #

- 1. Public Land Survey T5 N R5 W D-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

STATE OF MICHIGAN IONIA COUNTY RECEIVED FOR RECORD 16 NOV 95 4:19 P.M. DIANE H. ADAHS REGISTER OF DEEDS

Grid table with columns A-M and rows 1-13. Contains numbers 6-36.

I, MARINUS MULDER, in a field survey on AUGUST 21 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: THIS CORNER WAS NOT SET BY THE G.L.O. SURVEYORS. D.C. CRAWFORD FORMER IONIA COUNTY SURVEYOR ESTABLISHED THIS CORNER FEBRUARY 24 & 25, 1892 WHILE DOING A SECTIONAL SURVEY IN SECTION 32. THIS IS RECORDED IN VOLUME 2 PAGE 240 OF THE IONIA COUNTY SURVEYORS RECORDS. HE DID NOT STATE WHAT WAS SET OR SHOW ANY WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND REMAINS OF ROTTED ANCHOR POST NEXT TO A 20" CHERRY TREE AT THE INTERSECTION OF NORTH-SOUTH, EAST-WEST FENCE LINES. DUG AROUND BASE OF ANCHOR POST AND TREE AND FOUND SMALLER STONES BUT NOTHING SIGNIFICANT. SET 3/4" X 36" STEEL ROD AT BASE OF TREE. THIS IS ACCEPTED AS THE BEST HISTORICAL POSITION OF CRAWFORD'S CORNER OF 1892. DISTANCE FROM CENTER TO NORTH 1/4 CORNER = N 00°40'54" E 2637.19 FEET DISTANCE FROM CENTER TO EAST 1/4 CORNER = N 89°24'09" W 2650.87 FEET DISTANCE FROM NORTH 1/4 CORNER TO NORTHEAST SECTION CORNER = N 89°22'30" W 2641.14 FEET DISTANCE FROM EAST 1/4 CORNER TO NORTHEAST SECTION CORNER = N 00°28'13" E 2635.93 FEET

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: SET 3/4" X 36" STEEL BAR AT BASE OF 21" CHERRY TREE WITH A 2 3/4" DIAMETER CAP STATING "IONIA COUNTY P.S NO.25863." WITH THE FOLLOWING WITNESSES: NAIL & TAG SOUTHEAST SIDE OF 15" MAPLE N 60° E 40.08 FEET NAIL & TAG SOUTH SIDE 15" OAK N 81° E 46.06 FEET NAIL & TAG WEST SIDE 12" ASH N 28° E 23.53 FEET NAIL & TAG NORTHEAST SIDE 10" ELM S 28° E 14.60 FEET

Ratified by Peer Group P.A. 345 Ionia County Date Nov. 1, 1995 Marinus A. Mulder, Chairman

Signed by [Signature] Date 11-14-95 Surveyor's Michigan License No. 25863