

1993

COMMISSION

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
Diana M. DeWitt

93 SEP 21 P3:23

STATE OF MICHIGAN
IONIA COUNTY
RECEIVED FOR RECORD

For corners in

Form with fields for Location (Ionia), Corner Code (E-12), and survey details (Public Land Survey, Property Controlling, etc.)

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, Marinus Mulder, in a field survey on August 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, Lucious Lyon in 1826. Set wood post witnessed by: (1) 8" Ash S 48° W 6 links (2) 13" Ash S 83° E 15 links
Perpetuation: D.C. Crawford former Ionia County Surveyor perpetuated this coner in Feb. 24, 25, 1892 while doing a survey of Section 32. His witnesses are found as marginal notes on a copy of the County Surveyors G.L.O. notes. He states: (1) 3" Maple S 80° W 11 links (2) 4" Maple S 1° E 54 links.

Crawford's field survey is recorded in Volume 2 page 240 of the Ionia County Surveyors Books

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No 1892 witness trees remain. Found old fence line intersection. Dug at intersection and found too many stones to count, but found no evidence of Crawford's corner, if he did indeed set a clay cylinder.

Set corner in anchor post hole filled with stones and is accepted as the best available evidence of the postion of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 36" steel bar with a 2 3/4" diameter cap stating "Ionia County P.S. 25863" with the following witnesses:

- Nail & tag 10" Elm North 25.45'
Nail & tag 12" Poplar N 37° E 34.91'
Nail & tag 30" Maple N 78° W 43.18'
Nail & tag 30" Maple S 37° W 21.60
Centerline of ditch North 13'±

Signed by [Signature]

Date August 31, 1993

Surveyor's Michigan License No. 25863