

SURVEY & REMONUMENTATION

OCT 1 1 1994

COMMISSION

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia _____ (County)	Located In:	Corner Code #:
Public Land Survey	T 5N R 5W	F-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORDS
 94 JUN -6 P 3:52
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

Lot No. _____ Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5				4			3		2		1
3													
4	7	8				9			10		11		12
5													
6	18	17				16			15		14		13
7													
8	19	20				21			22		23		24
9													
10	30	29				28			27		26		25
11													
12	31	32				33			34		35		36

Marinus Mulder, in a field survey on November 10, 1993, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:
 This corner was first established by U.S. Deputy Surveyor, Lucious Lyon in 1827. A wood post was set witnessed by a 26" Oak N 49° E 6 links and a 21" Oak S 28° W 39 links.
 Perpetuation: D.C. Crawford former Ionia County Surveyor performed a sectional survey in Section 16 on December 10, 1887 found in Volume 1 page 416 of the Ionia County Surveyors Records. Crawford states he found the G.L.O. corner. It cannot be determined if he remonumented the corner. In the County Surveyors copy of the G.L.O. notes on page 27, Crawford has a marginal witness note for F-7. He states 1891: 12" Hickory N 41° E 55 links (36.30') and 10" Hickory S 56° E 56 links (36.96').

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Crawford's 12" Hickory witness tree still remains standing. Measured witness distance and excavated road bed and found a solid 2 1/4" diameter clay cylinder with stones at its base at a depth of 16". Accepted this as the corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set a 3/4" x 24" steel rod next to the clay cylinder with a 2 3/4" diameter cap stamped "P.L.S. 25863" witnessed by:
 Nail & tag Southwest side 20" Hickory S 52° E 36.72'
 Nail & tag South side 17" Oak S 85° E 25.84'
 Nail & tag North side 22" Oak S 77° W 45.16'
 Nail & tag South side 18" Hickory N 58° W 76.37'

Ratified by Peer Group
 P.A. 345 Ionia County
 Date 4-20-94 m.u.m.
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date April 29, 1994
 Surveyor's Michigan License No. 25863