

1993

REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia (County)

Located In:

Corner Code #

- 1. Public Land Survey T 5N R 5W G-3
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 93 DEC -7 P 3:40
 Doreen M. Robinson
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on September 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, Lucious Lyon in 1826. He set a wood post witnessed by (1) 9" White Oak S 16° E 21 links (2) 34" White Oak S89° W 10 links

Perpetuation: D.C. Crawford former Ionia County Surveyor did a sectional survey in Section 9 May 27 & 28 of 1884. This is recorded in Volume 1 page 344 & 345 of the Ionia County Surveyors records. He shows measurements to G-3 and says he found all old corners. In Volume 1, page 134 of the Ionia County Surveyors Records, A.C. Smith former County Surveyor in October of 1875 laid out a 1/8 line road in Section 10 but has no measurements to G-3. Crawford has marginal witness notes for this corner on a County Surveyors copy of the G.L.O. notes, referred to as the Red Book. He states: 1891 (1) 3" White Ash N 55° W 66 links (2) 14" Elm South 47 links. (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod and cap next to 2 1/4" clay cylinder with stones at base. Set 3/4" x 24" steel rod with 2 3/4" diameter cap in place of 1/2" rod. This is accepted as a perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 24" steel rod with a 2 3/4" cap stamped "Ionia County P.S. 25863" next to clay cylinder with the following witnesses:

- Nail & tag North side 12" Walnut S 60° E 45.77'
- Nail & tag South side 16" Hickory S 85° E 74.55'
- Nail & tag South side 10" Twin Poplar N 60° W 42.58'
- Nail & tag East side 8" Hackberry South 22.63'

Signed by _____ Date September 23, 1993
Surveyor's Michigan License No. 25863

Con't A: In June of 1979 I, Marinus Mulder, found a 2 1/4" clay cylinder with a early period broken Coca Cola bottle on top of cylinder. Crawford's 14" Elm witness of 1891 was a 36" stump. This corner is recorded in Liber 2 page 72. In 1979 set 1/2" rod and cap next to cylinder.