

SURVEY & REMONUMENTATION
APR 10 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in IONIA Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 5N R 5W _____ G-4 _____
 T _____ R _____ _____
 T _____ R _____ _____
 T _____ R _____ _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 94 DEC 29 P 1:58
 Dawn M. Adams
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

I, MARINUS MULDER, in a field survey on MARCH 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR LUCIUS LYON IN 1827. A WOOD POST WAS SET WITNESSED BY A 10" WHITE OAK S 21° W 36 LINKS AND A 18" WHITE OAK N 50° E 22 LINKS.
 PERPETUATION: D.C. CRAWFORD FORMER IONIA COUNTY SURVEYOR PERFORMED A SECTIONAL SURVEY IN SECTION 9, MAY 27 & 28, 1884, RECORDED IN VOLUME 1 PAGE 344 OF THE COUNTY SURVEYORS RECORDS. CRAWFORD SHOWS THE EAST 1/4 CORNER BUT DOES NOT SAY WHAT IT IS. ON PAGE 23 OF THE IONIA COUNTY SURVEYORS COPY OF THE G.L.O. NOTES CRAWFORD HAS A MARGINAL WITNESS NOTE FOR G-4 WHICH IS "1891, NO WITNESS, PILE STONES" A MAN CALLED SCHAFFER ALSO HAS A MARGINAL WITNESS NOTE WHICH READS: "1923, BETWEEN 3 CORNER FENCE POSTS, NORTHWEST OF STONE PILE".
 PROFESSIONAL SURVEYOR, JAMES PORTER NO. 19003 RECORDED G-4 OCTOBER 1, 1976. FOUND A CLAY MONUMENT ON THE WEST SIDE OF A 8" CONCRETE FENCE POST AND SET A #4 REBAR WITH CAP NEXT TO THE CLAY CYLINDER. PORTER WITNESSED THE CYLINDER WITH 3 OBJECTS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND A 2 1/4" DIAMETER VITRIFIED CLAY CYLINDER AT THE SOUTHWEST CORNER OF A 6" X 6" X 5' CONCRETE POST AT THE INTERSECTION OF FENCE LINES RUNNING NORTH, SOUTH, EAST AND WEST. D.C. CRAWFORD WAS KNOWN FOR HAVING SET MANY CLAY CYLINDERS IN IONIA COUNTY. ALSO FOUND PORTERS #4 ROD AND CAP NEXT TO CYLINDER. ACCEPTED THE CYLINDER AS THE PERPETUATED CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET A 3/4" X 36" STEEL ROD WITH A 2 3/4" DIAMETER CAP STAMPED "IONIA COUNTY - P.L.S. 25863" ON THE NORTH SIDE OF THE CYLINDER (REPLACING #4 ROD)
 WITNESSED BY:
 NAIL & TAG SOUTH SIDE 6" OAK N 50° W 4.18'
 NAIL & TAG WEST SIDE 36" OAK N 25° W 7.36'
 NAIL & TAG EAST SIDE 12" OAK S 15° W 23.33'
 NAIL & TAG NORTHEAST SIDE 4" CHERRY S 75° E 10.29'

Ratified by Peer Group
 P.A. 345 Ionia County
 Date 12-22-94
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date 12-27-94
 Surveyor's Michigan License No. 25863