

DEC 20 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

IONIA

(County)

Located In:


Corner Code #



LIBER 4

PAGE 136

- 1. Public Land Survey T5 N R5 W G-11
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims



Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on JUNE 28 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR, LUCIUS LYON IN 1827. A WOOD POST WAS SET AND WITNESSED BY A 11" MAPLE S 11° W 43 LINKS, AND A 10' ASH S 63° E 28 LINKS.

PERPETUATION: D.C. CRAWFORD FORMER IONIA COUNTY SURVEYOR HAS A MARGINAL WITNESS NOTE FOR G-11 ON PAGE 20 OF THE IONIA COUNTY SURVEYORS COPY OF THE G.L.O. NOTES. CRAWFORD'S WITNESS - "1891- 8" SUGAR S 75° E 63 LINKS, AND 14" MAPLE S 60° W 94 LINKS. CRAWFORD WAS KNOWN FOR SETTING 2 1/4" DIAMETER GLAZED CLAY TILE FOR MONUMENTATION.

THE IONIA COUNTY ROAD COMMISSION IMPROVED AND PAVED CHARLOTTE HIGHWAY BUT NO DATE COULD BE FOUND.

THE IONIA COUNTY ROAD COMMISSION HAS NO WITNESSES FOR G-11 IN THE WITNESS INDEX SHEETS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
AT THE INTERSECTION OF CHARLOTTE HIGHWAY AND TUPPER LAKE ROAD FOUND A 3/4"x12" BOATSPIKE 6" BELOW ROAD SURFACE. BELOW SPIKE AT A DEPTH OF 25" FOUND A BROKEN 2 1/4" GLAZED CLAY CYLINDER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
REPLACED EXISTING MONUMENTATION WITH A 7/8"x24" STEEL ROD WITH A 4" DIAMETER ALUMINUM CAP STAMPED - "IONIA COUNTY - P.S. 25863" WITNESSED BY:

- NAIL AND TAG S.E. SIDE POWER POLE N32°E 83.09'
- NAIL AND TAG N.W. SIDE POWER POLE S71°W 83.76'
- NAIL AND TAG N.E. SIDE POWER POLE N55°W 152.11'
- TOP CENTERLINE M.B.T. BOX S22°W 82.81'

Signed by Marinus A. Mulder Date 11-8-00

Surveyor's Michigan License No. 25863

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983



Ratified by Peer Group
P.A. 345 Ionia County

Date 7-19-2000
Marinus A. Mulder, Chairman