

SURVEY & REMONUMENTATION

OCT 07 1993

REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ionia</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>5N</u> R <u>5W</u>	<u>H-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 93 SEP 21 P 3:22
 REGISTER OF DEEDS
David M. DeBruin

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marinus Mulder, in a field survey on August 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner set by U.S. Deputy Surveyor Lucious Lyon in 1826. He set a wood post witnessed by: (1) 12" White Oak S 51° E 3 links (2) 7" Maple N 24° W 30 links. Perpetuation: D.C. Crawford former Ionia County Surveyor has marginal witness notes for this corner on the County Surveyors copy of the G.L.O. notes. He stated 1891: (1) 6" Walnut S70°E 81 links (2) 2" White Oak N 40°W 42 links. I, Marinus Mulder, in June 1979 found Crawford's cylinder of 1891 and set a 1/2" rod and cap which was recorded in Liber 2, page 130.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found rod and cap and Crawford's clay cylinder with stones at base, and accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 1/2" rod and cap and replaced with a 3/4" x 36" long steel bar with a 2 3/4" diameter cap stating "Ionia County P.S. 25863" with the following witnesses:

- Nail & tag 4" Maple S 57° E 30.92'
- Nail & tag 5" Ash S 19° E 19.18'
- Nail & tag 12" Ash S 74° W 68.07'
- Nail & tag 4" Ash N 12° W 36.63'

Signed by *Marinus Mulder* Date: August 30, 1993

Surveyor's Michigan License No. 25683

filed 10/11/93