

1993

REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia  
(County)

Located In:

Corner Code ==

- 1. Public Land Survey T 5N R 5W L-9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 IONIA COUNTY  
 RECEIVED FOR RECORDS  
 '93 DEC -7 P 3:40  
 REGISTER OF DEEDS  
*Oliver M. Adams*

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on September 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
Original corner set by U.S. Deputy Surveyor, Lucious Lyon in 1826. Set wood post witnessed by (1) 8" White Oak S 58° W 7 links (2) 6" Black Oak S 53° E 35 links.

Perpetuation: D.C. Crawford former Ionia County Surveyor performed a sectional survey of Section 24, November 19 & 20, 1891 which is recorded in Volume 2 page 214 of the Ionia County Surveyors records. Crawford shows measurements and the witnesses are found as marginal notes in the County Surveyors copy of the G.L.O. notes. Crawford writes 1891 (1) 8" White Oak S 43° E 32 links (2) 8" White Oak S 60° E 51 1/2 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 3/4 steel bar 30" long with no record or information who set it. Witnessed bar and excavated road bed with a backhoe opposite fence line to the North but found no stone or clay cylinder. None of Crawford's witness trees remain from 1891. The position of the bar measures very good to Government Corners West & East and to the center North. Replaced 3/4" bar with a 3/4" x 36" steel bar and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 3/4" x 36" steel bar with a 2 3/4" diameter cap stating "Ionia County P.S. 25863" with the following witnesses.

- Nail & tag West side 36" Oak N 17° E 38.34'
- Nail & tag East side power pole N 40° E 75.06'
- Nail & tag South side 8" Cherry N 75° E 42.97'
- Nail & tag North side 40" Oak S 57° E 51.77'

Signed by \_\_\_\_\_ Date September 20, 1993  
Surveyor's Michigan License No. 25863