

1993

REMONUMENTATION CORNER

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>5N</u> R <u>5W</u> | <u>L-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Oliver M. DeWitt
 REGISTER OF DEEDS

93 SEP 21 P 3:23

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORDS

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on June 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner set by U.S. Deputy Surveyor, Lucious Lyon, 1827. Set wood post witnessed by (1) 15" Beech S23°W 5 links (2) 6" Beech N53°E 20 links. Perpetuation: D.C. Crawford former Ionia County Surveyor in 1891 has marginal witness notes for this corner in a copy of the G.L.O. notes. He state (1) 2" Sugar Maple N50°E 144 1/4 links (2) 12" Apple N10°W 107 links. These notes are found in one of the County Surveyors Books for Ionia County referred to as "The Red Book" Crawford also makes reference to this corner as being a tile while performing a survey which is recorded in Volume 3 page 18 of the Ionia County Surveyors Books. No date given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" pipe and cap next to clay cylinder. Pipe set by P.S., Richard Steadman #11370. Steadman says that he found Crawford's clay cylinder with stones at base. The date was April 27, 1977. This is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Removed 1/2" pipe (left cylinder) and set 3/4" x 24" steel bar with 2 3/4" cap stating "Ionia County P.S. 25863".

Witnesses:
 S. W. Corner barn N 35° W 138.45'
 S.E. Corner barn N 10° W 113.38'
 Nail and tag power pole N 55° E 106.12'
 1/2" rod and cap North 33.00'

Signed by Marinus Mulder Date August 30, 1993

Surveyor's Michigan License No. 25863