

SURVEY BY
 PERMANENT
 APR 10 1995
 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in IONIA (County) Located in: _____ Corner Code # _____

1. Public Land Survey T 5N R 6W K-9
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 94 DEC 29 P1:57
 REGISTER OF DEEDS
Deane M. Deane

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

I, MARINUS MULDER, in a field survey on 7-28 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR, LUCIUS LYON IN 1827. A WOOD POST WAS SET AND WITNESSED BY A 18" SUGAR N 22° E 5 LINKS AND A 18" SUGAR S 41° W 30 LINKS.

THERE IS NO RECORD OF COUNTY SURVEYOR PERPETUATION OF K-9.
 THE IONIA COUNTY ROAD COMMISSION RECONSTRUCTED AND PAVED MUSGROVE HIGHWAY IN 1964. PLAN INFORMATION IS FOUND ON SHEET NO. 4 OF PROJECT NO. S 544. THE PLANS CALL FOR AN AXLE SHAFT WITNESSED BY:
 POWER POLE NORTHEAST 55.44'
 STEEL FENCE POLE NORTHWEST 41.28'
 TELEPHONE POLE SOUTHWEST 46.35'
 SIGN POST SOUTHWEST 37.20'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NAIL & TAG AT ROAD SURFACE AT DEPTH OF 12". FOUND A LARGE STONE. THE AXLE SHAFT WAS ON THE WEST SIDE OF THE STONE. ACCEPTED THE STONE AND AXLE SHAFT AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A 12" MONUMENT OVER THE TOP OF THE AXLE SHAFT AND STONE WITH A 4" DIAMETER BRONZE CAP. STAMPED "IONIA COUNTY SURVEY MONUMENT - DO NOT DISTURB" WITNESSED BY:
 NAIL & TAG EAST SIDE 6" ELM N 19° W 61.69'
 NAIL & TAG EAST SIDE POWER POLE N 33° E 55.56'
 CENTERLINE 4" STEEL POST N 38° W 41.30'
 TOP CENTERLINE OF M.B.T. BOX S 56° W 47.42'

Ratified by Peer Group
 P.A. 345 Ionia County

Date 10-20-94
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date 12-27-94

Surveyor's Michigan License No. 25863