

SURVEY & REMONUMENTATION

FEB 18 1994

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Ionia (County) Located In: Corner Code M-6

1. Public Land Survey T 5N R 6W _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

93 DEC 27 P 1:13

Duane M. Ankrom
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marinus Mulder, in a field survey on October 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 This corner was first set by U.S. Deputy Surveyor, Lucious Lyon in 1827. A wood post was set witnessed by a 6" Beech S 37° W 49 links and a 8" Sugar N 49 1/2° W 23 links. PERPETUATION:
 C. Crawford former Ionia County Surveyor performed a full sectional survey of Section 13, August 23, 1883. This survey is found in Volume 2, page 288 of the Ionia County Surveys Records. Crawford states he found the "Old Corners" but does not say what he used to perpetuate them. Also he showed no witnesses. The Ionia County Road Commission shows witnesses to this corner which were taken when Keefer Highway was being reconstructed for paving in 1962. They call for a 1" iron, but do not state what was found. This corner was recorded by Professional Surveyor, Duane Ankrom #1265 in April of 1977 found in Liber 1 page 234 of Ionia Corner records. Ankrom states he found a boat spike and set a re-rod and cap witnessed by 3 objects.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Ankrom's 1/2" rod and cap at surface of pavement. 10" below road surface found a 1" boat spike. 27" below road surface found a 1" boat spike. 30" below paved surface found a large stone. We drove the last boat spike down, which was next to the stone and set a 30" fiberglass monument over the 1" boat spike for the position of M-6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set a 30" fiberglass monument with a 4" diameter bronze cap stamped "Ionia County Survey Monument - Do Not Disturb" with the following witnesses:
 Nail & tag North side 4" wooden post N 84° W 26.58'
 Nail & tag Southeast side 5" Osage Orange S 31° W 75.04'
 Nail & tag Southwest side 6" Boxelder S 40° E 85.96'
 West 1/4 corner Section 18 T5N-R5W South 14.83'
 Nail & tag Northwest side 6" Boxelder N 29° E 39.80'

Signed by *Marinus Mulder* Date November 2, 1993
 Surveyor's Michigan License No. 25863