

*David M. Mulder*  
REGISTER OF DEEDS

SURVEY &  
REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in \_\_\_\_\_ Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T5N\_ R 7W\_ G-10  
 T\_\_\_\_ R\_\_\_\_  
 T\_\_\_\_ R\_\_\_\_  
 T\_\_\_\_ R\_\_\_\_

2. Property Controlling S\_\_\_\_ T\_\_\_\_ R\_\_\_\_  
 in Section S\_\_\_\_ T\_\_\_\_ R\_\_\_\_

3. Miscellaneous S\_\_\_\_ T\_\_\_\_ R\_\_\_\_  
 Property in Sec. S\_\_\_\_ T\_\_\_\_ R\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, MARINUS MULDER, in a field survey on 3-17 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required, in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR, JOHN MULLETT IN 1830. A WOOD POST WAS SET WITNESSED BY A 12" BEECH S 49° E 19 LINKS AND A 12" BEECH N 23° W 21 LINKS.  
PERPETUATION: THOMAS CORNELL FORMER IONIA COUNTY SURVEYOR PERFORMED THIS SECTIONAL SURVEY, OCTOBER 28 OF 1873. CORNELL DID NOT STATE WHAT WAS SET FOR G-10 BUT DOES SHOW STAKE AND STONES FOR OTHER CORNERS IN THE SECTION THIS SURVEY IS FOUND IN VOLUME 1 PAGE 36 OF THE COUNTY SURVEYORS RECORDS.  
THE IONIA COUNTY ROAD COMMISSION RECONSTRUCTED AND PAVED JORDAN LAKE ROAD IN 1967. THE PROJECT NUMBER WAS C-153. THE SHEETS FOR THIS SECTION OF ROAD COULD NOT BE FOUND. THE ROAD COMMISSION MASTER WITNESS MAP CALLS FOR 6 WITNESS OBJECTS FOR G-10.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" X 12" BOAT SPIKE 1" BELOW PAVED SURFACE AT INTERSECTION OF JORDAN LAKE ROAD AND BONANZA ROAD. DUG TO A DEPTH OF 20" AND FOUND A STONE PILE.  
ACCEPTED THE STONE PILE AS THE BEST AVAILABLE EVIDENCE OF THE PERPETUATION OF THE ORIGINAL CORNER.

C: Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 7/8" X 18" SOLID IRON BAR WITH A 4" DIAMETER BRONZE CAP STAMPED "IONIA COUNTY SURVEY MONUMENT - DO NOT DISTURB" IN PLACE OF THE BOAT SPIKE WITNESSED BY:  
NAIL & TAG NORTHEAST SIDE POWER POLE N 42° W 43.96'  
NAIL & TAG SOUTHEAST SIDE POWER POLE N 46° E 43.93'  
NAIL & TAG NORTHEAST SIDE POWER POLE S 21° E 50.43'  
NAIL & TAG SOUTHEAST SIDE POWER POLE S 50° W 52.15'

Ratified by Peer Group  
P.A. 345 Ionia County

Date 10-20-94  
Marinus A. Mulder, Chairman

BOOK 003 PAGE 131

Signed by Marinus A. Mulder Date 11-1-94

Surveyor's Michigan License No. 25863