

OCT 11 1994

REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

corners in

Located In: \_\_\_\_\_ Corner Code ## \_\_\_\_\_

Ionia (County)

Public Land Survey T 5N R 7 W L-13

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Diane M. Adams*  
REGISTER OF DEEDS

94 JUN -6 P 3:53

STATE OF MICHIGAN  
IONIA COUNTY  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Marinus Mulder, in a field survey on December 3, 1993, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

This corner was first established by U.S. Deputy Surveyor, John Mullett in 1830. A wood post was set witnessed by a 6" Thornapple N 66° E 19 links and a 30" Butternut N 14° W 23.1/2 links. There is no written record of this corner being perpetuated by the County Surveyor. The North 1/4 corner of Section 1, T4N-R7W, Barry County, according to G.L.O. should be West a distance of 16 feet, more or less according to averaging of the closing distances.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 falls in a gravel road. The North 1/4 corner of Section 1, T4N-R7W, was not found when an excavation was made with a backhoe. However there is an occupation fence running South along the North-South 1/4 line. A measurement of 16.17 feet East of the fence line was made and the area was excavated with a backhoe. A large round stone with a large cut stone was found 16" below the gravel road surface. A modern fence which runs North from the section line was built across from the North-South 1/4 line fence for Section 1. Accepted the stones as the position for L-13.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 24" steel bar with a 2 3/4" diameter cap stamped "P.S. 25863"  
Witnessed by:  
Nail & tag West side power pole N 27° W 27.60'  
South face of steel fence post N 3° E 26.88'  
South face of steel fence post N 51° E 38.29'  
1/2" rod & cap S 35° W 37.10' #25863  
North 1/4 corner Section 1, T4N-R7W West 16.17' (1/2" rod and cap)

Ratified by Peer Group  
P.A. 345 Ionia County

Date 4-20-94 *MCA-M*  
Marinus A. Mulder, Chairman

Recorded by Marinus A. Mulder Date 4-21-94

Surveyor's Michigan License No. 25863