

SURVEY & REMONUMENTATION

OCT 07 1993

COMMISSION

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ionia</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>5N</u> R <u>8W</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Oliver M. DeWitt
 REGISTER OF DEEDS

93 SEP 21 P 3:24

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marinus Mulder, in a field survey on June 24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by John Mullett U.S. Deputy Surveyor April 25, 1831 to August 7, 1831. A post witnessed by (1) 7" Elm N 52° W 12 links (2) 48" Lynn S2°E 7 links

Perpetuation: D.C. Crawford former Ionia County Surveyor re-set this corner while performing a sectional survey May 8 & 10, 1884 of Section 32 recorded in Volume 1 page 360 of the County Surveyors Records. He states he set a stake and stone witnessed by: 10" Butternut N 79 1/2° W 60 links, 12" Oak S 7° W 50 1/4 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched for stone at old fence line intersection but did not find. Held old fence line intersection and accepted as the best available evidence of the position of the original corner. Set 3/4" x 36" steel rod at fence intersection

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 36" steel rod with 2 3/4" cap stating "Ionia County P.S. 25863".

Witnesses:

- Nail & tag East side 6" Ash N 5° W 20.97'
- Nail & tag North side 10" Ash S 60° W 20.43'
- Nail & tag North side 12" Mulberry N 65° E 29.34'
- Nail & tag North side 12" Ash East 13.96'
- Nail & tag East side 12" Ash N 40° E 29.27'
- 8" wood post 2' Southeast

LIBER 003 PAGE 27

Signed by *Marinus Mulder* Date August 30, 1993
 Surveyor's Michigan License No. 25863

filed 10/11/93