

REMONUMENTATION CORNER

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OCT 1 1 1994

Ionia COMMISSION Located In: _____ Corner Code ##

- 1. Public Land Survey T 5N R 8W _____ G-2
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORDS
 94 JUN -6 P 3:52
 Diane M. DeWitt
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on October 25, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, John Mullett in 1830. A wood post was set witnessed by a 5" beech S 14° W 5 links and a 11" Sugar N 45° E 10 links.
 PERPETUATION: A.C. Smith, former Ionia County Surveyor performed a sectional survey in Section 3, December 1 & 2, 1875. Smith calls for a stake & stone for G-2 but gives no witnesses. This survey is found in Volume 1 page 152 of the County Surveyors records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No occupation lines running East or West remain. Excavated gravel road with a backhoe and found large stone with smaller stones at base. The distance to the Southwest section corner measures good. Accepted the stone as the corner and placed a 3/4" x 36" steel rod next to the stone. The stone was about 18" deep.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 36" steel rod with a 2 3/4" diameter cap stamped "P.S. 25863" next to stone.
 Witnessed by:
 Nail & tag Northwest side 10" Elm Southwest 22.80'
 Nail & tag South side triple Maple East Northeast 22.16'
 Nail & tag East side 16" Maple Southwest 42.03'
 Nail & tag West side 5" Cherry Northeast 72.33'

Ratified by Peer Group
 P.A. 345 Ionia County

Date 4-20-94 M.A.M.
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date April 29, 1994
 Surveyor's Michigan License No. 25863