

DEC 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 219

For corners in IONIA (County)

Located In: Corner Code #

- 1. Public Land Survey T5 N R8 W G-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

STATE OF MICHIGAN IONIA COUNTY RECEIVED FOR RECORD 16 NOV 95 4:20 P.M. DIANE M. ADAMS REGISTER OF DEEDS STAMP & FILE NUMBER

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Contains numbers 1-36.

I, MARINUS MULDER, in a field survey on FEBRUARY 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR, JOHN MULLETT IN 1830. A WOOD POST WAS SET WITNESSED BY A 10" ELM S 64° E LINKS AND A 7" BEECH S 78° W 15 LINKS. PERPETUATION: THERE IS NO RECORDED INFORMATION OF ANY COUNTY SURVEYS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND 1" PIPE IN CENTERLINE OF GRAVEL ROAD OPPOSITE FENCE LINE EAST & WEST. REMOVED PIPE AND EXCAVATED ROAD WITH A BACK HOE, AND 6 FEET NORTH OF A FENCE LINE RUNNING EAST-WEST AND AT A DEPTH OF 10" FOUND A LARGE CUT STONE. ACCEPTED THIS STONE AS THE CORNER. NOTE: FENCE LINE RUNNING EAST AND WEST IS NOT AN OLD FENCE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: SET A 3/4" DIAMETER X 24" LONG STEEL ROD WITH A 2 3/4" DIAMETER CAP STAMPED "IONIA COUNTY P.S. 25863" ON THE NORTH SIDE OF THE STONE. THE ROD IS WITNESSED BY: NAIL & TAG EAST SIDE 24" WALNUT N 20° W 62.72 FEET NAIL & TAG WEST SIDE 26" STUMP N 25° E 65.62 FEET SOUTHEAST EDGE ANGLE IRON POST S 82° W 25.57 FEET SOUTHWEST EDGE STEEL "U" BEAM POST S 73° E 30.27 FEET

Ratified by Peer Group P.A. 345 Ionia County

Date Nov. 1, 1995 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder

Date 11-14-95

Surveyor's Michigan License No. 25863