

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>5N</u> R <u>8W</u> | <u>H-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 93 DEC 27 P1:07
Oliver M. DeWitt
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on September 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 This corner was not set by the G.L.O. Surveyors. ESTABLISHMENT: No record of a county survey in Section 35 could be found. The Ionia County Road Commission makes reference to this corner in the County Road plans for Nash Highway. The plans calls for a 3/4" iron witnessed by: A power pole East 36.50 feet, telephone pole West 24.80 feet, and a telephone pole Northwest 119.40 feet. Professional Surveyor, William Rogers No. 6197, recorded this corner May 5, 1972 found in Liber 1 page 67. He states he found a 3/4" iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 A standard Ionia County nail & washer was found just below the paved road surface. At 2 feet below the surface a 3/4" boat spike was found. We dug to a depth of 36" but no other evidence was found. I decided to hold this position for the section center.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A 30" long fiberglass monument with a 4" diameter bronze cap stamped "Ionia County Survey Monument - Do not disturb" was set in place of the boat spike with the following witnesses:
 Nail & tag North side power pole S 70° E 36.43'
 Nail & tag South side 5" Mulberry clump N 50° E 44.68'
 Nail & tag West side 4" Ash S 7° E 122.80'
 (Note - no other objects near corner)

Signed by Marinus Mulder Date October 20, 1993
 Surveyor's Michigan License No. 25863