

**SURVEY &
REMONUMENTATION**

FEB 18 1994

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

<u>Ionia</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>8W</u>	<u>H-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 93 DEC 27 P 1:07
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on September 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, John Mullett in 1831: A wood post was set witnessed by: 11" Beech N 89° E 15 links and 6" Beech N 37° W 35 links. No record of County Survey restoration could be found. The Ionia County Road Commission makes reference to this corner in the County Road plans for Nash Highway. The plans called for a P.K. nail witnessed by a 1 1/4" iron Northeast 68.55 feet, a road sign South 18.45 feet and a telephone pole Southwest 83.65 feet. This was found on Sheet 3 of 4 for the Nash Highway plans of 1966.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found P.K. nail and below paved surface found 3/4" boat spike. Excavated to a depth of 30 inches but found no other evidence. This boat spike was accepted as the position for H-13. A 30" long fiberglass monument was set in its place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 30" long fiberglass monument with a 4" diameter bronze cap stamped "Ionia County Survey Monument - Do not disturb" with the following witnesses:

- Nail & tag West side power pole S 15° W 28.30 feet
- Southeast corner house foundation N 66° W 223.95 feet
- Nail & tag North side 12" White Pine S 55° W 56.78 feet
- Nail & tag Northeast side 2"-6" Maple clump S 40° E 54.36 feet

Signed by Marinus Mulder Date October 21, 1993
 Surveyor's Michigan License No. 25863