

SURVEY & REMONUMENTATION
APR 10 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners IONIA
 (County)

Located in:

Corner Code #

- 1. Public Land Survey T 5N R 8W I-2
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Oliver M. Robinson
 REGISTER OF DEEDS

'94 DEC 29 P 1:57

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

I, MARINUS MULDER, in a field survey on OCTOBER 28 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR JOHN MULLETT IN 1830. A WOOD POST WAS SET WITNESSED BY A 10" SUGAR N 3° E 9 LINKS AND A 9" SUGAR S 26° E 10 LINKS.
 PERPETUATION: A.C. SMITH FORMER IONIA COUNTY SURVEYOR PERFORMED A SECTIONAL SURVEY IN SECTION 3, DECEMBER 1 & 2, 1875, WHICH IS FOUND IN VOLUME 1 PAGE 152 OF THE IONIA COUNTY SURVEYORS RECORDS. SMITH CALLS FOR A STAKE AND STONE FOR I-2 BUT GIVES NO WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 EXCAVATED GRAVEL ROAD AND FOUND A CUT STONE WITH BROKEN CROCKERY AT ITS BASE AND A 1" PIPE NEXT TO THE STONE, WHICH WAS ABOUT 4" BELOW THE GRAVEL SURFACE. ACCEPTED THE STONE AS THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 REMOVED THE 1" PIPE AND REPLACED IT WITH A 2/4 X 36" STEEL ROD WITH A 2 3/4" DIAMETER CAP STAMPED "P.L.S. 25863"

WITNESSED BY:
 NAIL & TAG SOUTH SIDE POWER POLE N 89° W 49.30'
 NAIL & TAG NORTHWEST SIDE 22" MAPLE N 35° E 52.65'
 NAIL & TAG SOUTH SIDE 13" MAPLE N 80° E 74.36'
 SOUTHWEST CORNER OF HOUSE FOUNDATION N 58° E 99.92'

Rated by Peer Group
 P.A. 345 Ionia County

Date 12-22-94
 Marinus A. Mulder, Chairman

Signed by mad a mulder

Date 12-27-94

Surveyor's Michigan License No. 25863

BOOK **003** PAGE **165**