

1993

REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia (County) Located In: Corner Code --#
1. Public Land Survey T 5N R 8W J-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

93 SEP 21 P 3:24
STATE OF MICHIGAN
IONIA COUNTY
RECEIVED FOR RECORD
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on August 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column J and row 9.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, John Mullett, April 25 to August 7, 1831. Set a post witnessed by: (1) 8" White Oak S 30° E 21 links. (2) 16" White Oak N 15° E 28 links.

Perpetuation: D.C. Crawford former Ionia County Surveyor performed a sectional survey of Section 23, October 28 & 29, 1888 found in Volume 1, page 456 of Ionia County Surveyors Records. Does not state what he set. His witness is (1) 24" Maple S 27°45' W 1.39 chains.

I, Marinus A. Mulder, during a survey in March of 1981 found a 1" steel shaft 21" long with stones at base. I accepted this as the corner and recorded it in Liber 2, page 166.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found corner which I recorded in 1981 and accepted as a faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 1" x 21" steel shaft and set a 3/4" x 36" steel bar with a 2 3/4" cap stating "Ionia County P.S. 25863" with the following witnesses:

- Nail & tag 15" Walnut N 28° W 35.97'
Nail & tag 15" Basswood cluster N 71° W 31.80'
Nail & tag 10" Elm S 17° E 50.31'
Nail & tag 14" Elm S 89° E 42.50'

LIBER 003 PAGE 29

Signed by [Signature] Date August 30, 1993

Surveyor's Michigan License No. 25863