

REV

1993

REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS  
*Dianna M. Adams*

93 DEC -7 P 3:40

STATE OF MICHIGAN  
IONIA COUNTY  
RECEIVED FOR RECORD

For corners in

Ionia  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 6N R 5W      C-13  
                                   T \_\_\_\_\_ R \_\_\_\_\_  
                                   T \_\_\_\_\_ R \_\_\_\_\_  
                                   T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section               S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous           S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.         S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on September 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, Lucious Lyon in 1826. He set a wood post witnessed by a 6" Beech N 24° E 45 links & a 6" Beech N 44" W 15 links.

PERPETUATION: D.C. Crawford former Ionia County Surveyor remonumented Portland Township in the 1890's. Crawford has a marginal witness note in the County Surveyor's copy of the G.L.O. notes stating the following: 8" Cherry S 21° W 193 1/2 links; 8" Maple N 83 1/2° W 328 links. Crawford set 2 1/4" solid tile. I, Marinus Mulder, found this corner June 6 of 1982 and set a 5/8" rod and cap next to the cylinder. This is recorded in Liber 2 page 212.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rod and cap next to cylinder. Replaced 5/8" rod and cap with 3/4" x 24" steel rod and a 2 3/4" cap.

SURVEY &  
REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 24" steel rod with a 2 3/4" cap stating "Ionia County P.S. 25863" with the following witnesses:

Southwest corner of 12" x 12" concrete anchor post, North 32.18'

Nail & tag West side 6" Maple N 29° E 31.90'

Nail & tag North side power pole S 54° E 56.0'

Nail & tag telephone pole S 15° E 66.92'

Northwest corner Section 5, T5N-R5W, West 29.65'

Signed by \_\_\_\_\_ Date October 26, 1993

Surveyor's Michigan License No. 25863