

FEB 18 1994

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 6N R 5W E-7
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 93 DEC 27 P 1:05
 Diane M. Robbins
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on September 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by Lucious Lyon in 1827. He set a wood post witnessed by a 9" Black Oak S 20° E 34 links and a 18" Black Oak N 59° W 15 links.

RESTORATION: D.C. Crawford former Ionia County Surveyor, remonumented all of Portland Township in the 1890's. Most corners were remonumented with 2 1/4" glazed clay cylinders. Crawford's witnesses to these section corners are found as marginal notes on a copy of the G.L.O. notes located in a Ionia County Surveyor's volume. Crawford's marginal note for E-7 states the following: 1890, 8" Hickory N 62° E 102 1/2 links; 14" White Oak N 49° W 70 links. Professional Surveyor, George Stevenson #13600 found a 1/2" rod and accepted as the corner in September of 1975. This is recorded in Liber 1 page 183. In October of 1979 I recovered the clay (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod and cap on top of clay cylinder. Replaced 1/2" rod with 3/4" rod. Stevenson's recorded corner was 7 feet East of the cylinder.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" x 24" steel rod with a 2 3/4" diameter cap stamped "Ionia County, P.S. 25863" Witnessed by:

- Nail & tag Northeast side power pole N 68° W 92.33'
- Nail & tag North side 13" Elm S 73° E 91.10'
- Northwest corner concrete post S 40° E 43.65'
- Centerline of physical road (gravel) 7' East

Signed by Marinus Mulder Date October 26, 1993

Surveyor's Michigan License No. 25863

cylinder set by Crawford and set a 1/2" rod & cap on top of it. This is recorded in Liber 2 page 184.

~~Q. 17 - 6. 2~~