

**SURVEY & REMONUMENTATION**

FEB 18 1994

COMMISSION

REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ionia  
 (County)

Located In:

Corner Code ≠

- |                                    |                         |            |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey              | T <u>6N</u> R <u>5W</u> | <u>G-7</u> |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 IONIA COUNTY  
 RECEIVED FOR RECORD  
 93 DEC 27 P 1:14  
 Register of Deeds  
*Oliver M. Adams*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on July 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, Lucious Lyon in 1827: A wood post was set witnessed by a 20" White Oak N 80 1/2° W 23 links and a 22" White Oak N 86° E 15 links.  
 PERPETUATION: D. C. Crawford former Ionia County Surveyor remonumented Portland Township in 1890 & 1891. His witness notes are found as marginal notes next to the respective corner on the County Surveyors copy of the G.L.O. notes. Crawford's witnesses for G-7 are: 1890, 10" White Oak N 2° W 46 links and 12" Black Walnut S 32° W 56 links. Crawford used 2 1/4" diameter solid glazed clay tile cylinders for his monumentation.

I, Marinus Mulder in May of 1981 recovered the corner Crawford set in the 1890's, excavating the gravel road and finding a 2 1/4" diameter clay cylinder. A 5/8" rod & cap was set next to the cylinder. This corner is recorded in Liber 2 page 159 of the Ionia survey corner records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 5/8" rod and cap next to a 2 1/4" clay cylinder. Accepted this as the position for G-7 and replaced the 5/8" rod and cap with a 3/4" x 36" steel rod and cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 3/4" x 36" steel rod and 2 3/4" diameter cap stamped "Ionia County P.S. 25863" witnessed by:

Nail & tag East side 30" stump N 5° E 29.86' (This could possibly be one of Crawford's 1890 witnesses)

Nail & tag West side fence post S 04° W 43.18'

Nail & tag Northeast side 16" Hickory S 48° E 94.98'

Nail & tag Northeast side 14" Oak S 27° E 77.20'

Signed by Marinus Mulder Date October 28, 1993

Surveyor's Michigan License No. 25863