

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia (County)

Located In:

Corner Code #

- 1. Public Land Survey T 6N R 5W I-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

STATE OF MICHIGAN IONIA COUNTY RECEIVED FOR RECORD 93 DEC 27 P1:07

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on August 25, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, Lucious Lyon in 1827. He set a wood post witnessed by: 10" Ash S 62° E 7 links; 6" Ash N 71° W 8 links.

Perpetuation: D.C. Crawford former Ionia County Surveyor performed a survey in Section 23 on April 13-16, 1883, recorded in Volume 1, page 296 of the County Surveyors Records. He states all corners re-set but has no witnesses. In 1890 Crawford remonumented Portland Township and his witnesses to the Government Corners are shown as marginal notes in the County Surveyors copy of the G.L.O. notes. Crawford used 2 1/4" solid clay cylinders to remonument the corners. His witnesses for I-7 were 10" Maple N 22 1/2° W 51 links, 3" Elm S 4° E 50 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Position falls in a section line gravel road. Excavated road bed with a backhoe and found 2 1/4" clay cylinder with stones at base. Accepted this as a a perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 3/4" x 36" steel bar next to cylinder with a 2 3/4" cap stamped: "Ionia County P.S. 25863" with the following witnesses:

- Nail & tag West side 10" Hickory S 55° W 54.43'
Nail & tag North side 3" Elm N 78° E 50.67'
Nail & tag West side 8" Hickory North 41.77'
Nail & tag East side power pole N 20° W 28.65'

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column H and row 7.

Signed by [Signature] Date October 21, 1993
Surveyor's Michigan License No. 25863