

1993

REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 6N R 5W I-8
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Diane M. O'Brien
REGISTER OF DEEDS

93 DEC -7 P 3:40

STATE OF MICHIGAN
IONIA COUNTY
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on August 25, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
This corner was first set by U.S. Deputy Surveyor, Lucious Lyon in 1827. He set a wood post witnessed by: (1) 11" Hickory S 47° E 15 links (2) 11" Ash N 87° W 28 links.

Perpetuation: D.C. Crawford former Ionia County Surveyor performed a survey in Section 23 on April 13-16, 1883, recorded in Volume 1, page 296 of the County Surveyors Records. He states all corners re-set but has no witnesses. In 1890 Crawford remonumented Portland Township and his witnesses to the Government Corners are shown as marginal notes in the County Surveyors copy of the G.L.O. notes. Crawford showed no witnesses for this corner. Crawford used 2 1/4" solid clay cylinders to remonument the corners.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Position falls in a section line gravel road. Excavated road bed with a backhoe oposite fence line to the East. Found 2 1/4" clay cylinder with stones at base. Accepted this as a perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 3/4" x 36" steel bar next to cylinder with a 2 3/4" diameter cap stating; "Ionia County P.S. 25863. Witnessed by:
Nail & tag East side 10" Twin Elm N 30° W 22.83'
Nail & tag North side 22" Twin Walnut S 69° W 28.40'
Nail & tag East side 12" Walnut S 35° W 28.40'
Northeast Corner 12" x 12" concrete post S 75° E 19.63'

Signed by _____ Date September 20, 1993
Surveyor's Michigan License No. 25863