

SURVEY B
PERMANENT IDENTIFICATION
APR 10 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in IONIA (County) Located in: _____ Corner Code # _____

1. Public Land Survey T 6N R 6W _____ A-10
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

94 DEC 29 P2:00

Clara M. Adams
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, MARINUS MULDER, in a field survey on OCTOBER 28 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 THIS CLOSING CORNER WAS NOT SET BY U.S. GOVERNMENT SURVEYORS. LUCIUS LYON SURVEYED T6N-R6W IN 1827. IN THE GOVERNMENT NOTES LYON STATES HE INTERSECTED THE WEST TOWNSHIP LINE AT THE STANDARD POST FOR BOTH THE SOUTHWEST CORNER OF SECTION 30 AND THE NORTHWEST CORNER OF SECTION 30. THERE ARE NO RECORDED SURVEYS FOR SECTION 30 OR FOR SECTION 25, T6N-R7W.
 PERPETUATION - THIS CORNER FALLS AT THE INTERSECTION OF MICHIGAN HIGHWAY M-66 AND INTERSTATE I-96. HIGHWAY M-66 PLANS SHOW NO WITNESSES FOR THIS CORNER. THE IONIA COUNTY ROAD COMMISSION WITNESS MAP SHOW THE FOLLOWING WITNESSES FOR THIS CORNER: 3/8" STEEL PIN; 24" ELM S 89° W 64.26 FEET, 6" ELM EAST 94.20 FEET, 2" ELM N 47° E 54.40 FEET. THE MICHIGAN DEPARTMENT OF TRANSPORTATION HIGHWAY PLANS FOR INTERSTATE 96 PROJECT 34044, SHEET T-30-B-1 SHOW THE SAME WITNESSES AS THE IONIA ROAD COMMISSION, WHICH IS DATED OCTOBER 1957. THIS PIN WAS IN PLACE BEFORE CONSTRUCTION OF I-96 AND RECONSTRUCTION OF THAT PORTION OF M-66 NEAR I-96. THE STANDARD CORNER (M-10, T6N-R7W) WAS SET BY U.S. DEPUTY SURVEYOR, LUCIUS LYON IN 1830 WHICH WAS A WOOD POST WITNESSED BY A 7" BEECH S 41° W 21 LINKS AND A 11 BEECH N 33° W 18 LINKS.
 I, MARINUS A. MULDER, FOUND THE 1" IRON PIN AND RECORDED IT MAY OF 1982 IN LIBER 2 PAGE 165 AND MEASURED TO 4 WITNESS OBJECTS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1" CRIMP TOP PIPE IN MEDIAN OF M-66 AND I-96 INTERCHANGE. ALL PREVIOUS HIGHWAY WITNESSES ARE GONE. MY WITNESS OBJECTS OF 1982 STILL REMAIN. THE DISTANCE TO CORNER A-11 MEASURES 2635.06 FEET
 ACCEPTED THIS AS THE BEST AVAILABLE EVIDENCE FOR A-10.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 REPLACED 1" CRIMP TOP PIPE WITH A 3/4" X 24" STEEL ROD WITH A 2 3/4" DIAMETER CAP STAMPED P.L.S. 25863 WITNESSED BY:
 TOP SOUTHWEST CORNER OF CONCRETE BRIDGE RAIL N 44° E 26.91 FEET.
 TOP SOUTHEAST CORNER OF CONCRETE BRIDGE RAIL N 27° W 26.77 FEET.
 NORTHWEST CORNER OF STEEL CURB OF CATCH BASIN S 65° E 18.52 FEET.
 NAIL & TAG TOP OF 6" X 6" WOOD GUARD POST S 33° W 28.97 FEET.

Ratified by Peer Group
P.A. 345 Ionia County

Date 12-22-94
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date 12-27-94

Surveyor's Michigan License No. 25863 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971