

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia  
(County)

Located In:

Corner Code =#

- 1. Public Land Survey      T 6N R 6W      C-2
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section               S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous           S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec.         S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

*Clayton M. Adams*  
REGISTER OF DEEDS

93 DEC 27 P 1:08

STATE OF MICHIGAN  
IONIA COUNTY  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	•	5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on September 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
This corner was first set by U.S. Deputy Surveyor, (Lucious Lyon). A wood post was set witnessed by a 26" Beech S50°W 25 links and a 10" Beech N60°E 11 links. This was set in 1827.  
There is no County Surveyors record of perpetuation of this corner.

In May of 1978 Professional Surveyor, Paul VanKooten #8618 set a T iron at the intersection of fences. This is recorded in Liber 2, page 22 Ionia Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
No early historical evidence was found here.  
Found T iron and accepted this as the position of C-2. A 3/4" x 36" steel rod was set over the T iron.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET a 3/4" x 36" steel rod and a 2 3/4" diameter cap stamped "Ionia County P.S. 25863" witnessed by:

- Nail & tag North side 10" Oak S 82° E 7.77'
- Nail & tag North side twin 8" Maple S 25° E 21.67'
- Nail & tag West side 8" Poplar N 50° W 29.92'
- Nail & tag North side 4" Poplar S 80° W 25.41'
- Railroad tie post 0.7' East

Signed by Marinus Mulder Date October 26, 1993

Surveyor's Michigan License No. 25863