

DEC 20 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970


For corners in IONIA (County)

Located In: Corner Code #



LIBER 4 PAGE 134

- 1. Public Land Survey T6 N R6 W I-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims



Register of Deeds Stamp & File Number

I, MARINUS MULDER, in a field survey on MAY 17 2000,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR, LUCIUS LYON IN 1827 . A 10" WHITE OAK WAS CALLED AS THE CORNER FOR I-13.

PERPETUATION: THERE IS NO RECORDED COUNTY SURVEY INFORMATION FOR I-13. HOWEVER D.C. CRAWFORD FORMER COUNTY SURVEYOR PERFORMED A SURVEY OF SECTION 3, T5N-R6W RECORDED ON PAGE 220, VOLUME 2 OF IONIA COUNTY SURVEY RECORDS. NO INFORMATION WAS SHOWN FOR I-13, T5N-R6W.

THE IONIA COUNTY ROAD COMMISSION IMPROVED AND PAVED SUNFIELD HIGHWAY IN 1964, PROJECT NO. CS34-71. THE ROAD PLANS ON SHEET 4 CALL FOR A BOAT SPIKE WITNESSED BY:
8" WALNUT N.W. 28.00 FEET
18" MAPLE S.E. 43.20 FEET
12" ELM N.E. 53.50 FEET
SIGN POST N.E. 31.80 FEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: AT THE INTERSECTION OF KNOX AND SUNFIELD HIGHWAY AND BELOW THE TAR AND CHIP ROAD SURFACE A NAIL AND TAG WAS FOUND. EXCAVATED BELOW NAIL AND TAG AND AT A DEPTH OF 16" FOUND A 3/4" X 12" BOATSPIKE. AT A DEPTH OF 20" FOUND 2 POINTED STONES ABOUT 14" LONG. NO COUNTY WITNESSES REMAIN.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: REPLACED EXISTING MONUMENTATION WITH A 7/8"x24" STEEL ROD WITH A 4" DIAMETER ALUMINUM CAP STAMPED - "IONIA COUNTY - P.S. 25863" WITNESSED BY:

- NAIL AND TAG SW. SIDE 10" ASH N57°W 26.46'
NAIL AND TAG S. SIDE 34" OAK N74°E 65.93'
NAIL AND TAG W. SIDE POWER POLE S11°E 111.98'
SE. CORNER OF MAIN PART OF HOUSE FOUNDATION N24°W 147.13'
NW. CORNER SEC. 2, T5N-R6W 7/8"x24" ROD WITH 4" DIAMETER CAP EAST 3.30'

Table with 13 rows and 12 columns (A-L) containing numbers 1-36.

Signed by [Signature] Date 11-8-00
Surveyor's Michigan License No. 25863

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1989



Ratified by Peer Group
P.A. 345 Ionia County
Date 7-19-2000
Marinus A. Mulder, Chairman