

SURVEY & REMONUMENTATION COMMISSION
APR 10 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in IONIA
 (County)

Located In:

Corner Code #

- 1. Public Land Survey T 6N R 6W K-5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, MARINUS MULDER, in a field survey on OCTOBER 3 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER WAS FIRST SET BY U.S. DEPUTY SURVEYOR, LUCIUS LYON IN 1827. A WOOD POST WAS SET WITNESSED BY A 15" BEECH S 24° E 24 LINKS AND A 13" LYNN N 87° E 14 LINKS.
 PERPETUATION: D.C. CRAWFORD FORMER IONIA COUNTY SURVEY PERFORMED A SECTIONAL SURVEY IN SECTION 11, DECEMBER 6-8, 1888 FOUND IN VOLUME 1, PAGE 470 OF THE IONIA COUNTY SURVEYORS RECORDS. CRAWFORD STATES HE FOUND THE OLD CORNER BUT DOES NOT SAY IF HE REMONUMENTED IT. CRAWFORD ALSO PERFORMED A SECTIONAL SURVEY IN SECTION 12, DECEMBER 5 & 6 OF 1888. FOUND IN VOLUME 1, PAGE 468. HE STATES FOR K-5 "CORNER AS FOUND" WITH NO OTHER INFORMATION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

EXCAVATED ROAD BED WITH A BACK HOE AND FOUND A LARGE STONE WITH BROKEN CROCKERY AROUND IT AT A DEPTH OF 10". ACCEPTED THIS AS THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A 3/4 X 24" STEEL BAR WITH A 2 3/4" DIAMETER CAP STAMPED "P.L.S. 25863 NEXT TO THE STONE WITNESSED BY:
 CENTERLINE 4 1/2" STEEL POST SOUTH 26.57'
 NAIL & TAG POWER POLE NORTH 49.26'
 NAIL & TAG SOUTHEAST SIDE 10" WALNUT N 43° E 40.66'
 NAIL & TAG SOUTHEAST SIDE 8" WALNUT N 71° E 74.78'

REGISTER OF DEEDS
James M. O'Brien

94 FEB 29 P 2:00

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Ratified by Peer Group
 P.A. 345 Ionia County

Date 12-22-94

Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder

Date 12-27-94

Surveyor's Michigan License No. 25863