

SURVEY & REMONUMENTATION

OCT 11 1994

COMMISSION

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

James M. Adams
REGISTER OF DEEDS

94 JUN -6 P 3:54

STATE OF MICHIGAN
IONIA COUNTY
RECEIVED FOR RECORD

For corners in

Ionia (County) Located In: Corner Code ##

1. Public Land Survey T 6N R 6W L-1
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Marinus Mulder, in a field survey on October 20, 1993,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This closing corner was not set by the G.L.O. Surveyors.
 Establishment or Perpetuation: D.C. Crawford former Ionia County Surveyor performed a sectional survey of Section 1, November 20-22, 1883. Recorded in Volume 2 page 292 of the Ionia County Surveyors Records. Crawford shows no witnesses or what he set for the corner. The prorated jog distance to the standard corner for T7N-R6W is 13 links West. This corner was recorded by Professional Surveyor, Marinus Mulder, June 29, 1987 found in Ionia County Public Act 74 recordation file Liber 2 page 350. A large stone was found in (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone and 5/8" rod and cap as noted in 1987 and accepted as the corner. removed 5/8" rod and set a 3/4" bar and cap in place of it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 24" steel bar with a 2 3/4" diameter cap stamped "P.S. 25863"
 Witnessed by:
 Nail & tag South side 14" Walnut N 43° W 36.18'
 Nail & tag Southeast side 12" Walnut N 33° E 19.06'
 Nail & tag East side 32" Cherry S 28° W 21.35'
 Nail & tag Northeast side 8" Cedar S 55° E 44.62'

Ratified by Peer Group
 P.A. 345 Ionia County
 Date 4-20-94 *M.A.M.*
 Marinus A. Mulder, Chairman

Signed by *Marinus A. Mulder* Date 4-21-94

Surveyor's Michigan License No. 25863

the road bed opposite a fence line to the South, and a 5/8" rod and cap was set next to it, and 4 witnesses were taken.