

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia _____
 (County)

Located In:

Corner Code ##

- | | | | |
|------------------------------------|-------------|-------------|-------------|
| 1. Public Land Survey | T <u>6N</u> | R <u>6W</u> | <u>L-13</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Marinus Mulder, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, Lucious Lyon in 1827. He set a wood post witnessed by a 11" Beech N 66° E 30 links and a 8" Maple N 5° W 14 links.

PERPETUATION: D.C. Crawford former Ionia County Surveyor performed a survey in Section 1 of T5N-R6W, April 19 and 20, 1893. For L-13 he set a stake and stone. There was no township jog at this corner. Crawford showed no witnesses. In the County Surveyors copy of the G.L.O. notes there are marginal witness notes for L-13. The note says: "Schaffer 1923: 20" Elm S.S.W. 32.3', 24" Elm N.E. 43.3', 20" Maple N.W. 70.9' " I, Marinus Mulder, found a stone and brick May 5 of 1985. I set a 5/8" rod and cap next to the stone. This is recorded in Liber 2 page 321 of County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rod and cap next to stone as set in 1985. Replaced 5/8" rod with 3/4" x 24" steel rod with 2 3/4" cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 24" steel rod with a 2 3/4" diameter cap stating "Ionia County P.S. 25863" with the following witnesses:

- Nail & tag West side 26" Maple S 35° W 35.22'
- Nail & tag West side 12" Elm S 6° W 20.51'
- Nail & tag Northeast side 12" Ash S 30° E 23.33'
- Nail & tag 12" Hickory S 66° E 60.30'

Signed by Marinus Mulder Date October 26, 1993
 Surveyor's Michigan License No. 25863

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 93 DEC 27 P 1:13
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												