

JUL 1 9 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 102

For corners in SECTION  
IONIA  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>6</u> N	R <u>7</u> W	G-8
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN  
IONIA COUNTY  
RECEIVED FOR RECORD

23 NOV 99 3:03 P.M.

DIANE K. ADAMS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARINUS MULDER, in a field survey on JUNE 16 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR JOHN MULLETT IN 1831. A WOOD POST WAS SET WITNESSED BY A 14" SUGAR MAPLE S 06° W 17 LINKS AND A 7" BEECH NORTH 15 LINKS.

PERPETUATION: THERE ARE NO RECORDED COUNTY SURVEYS IN SECTION 21 OR 22 OF T6N-R7W.

THE IONIA COUNTY ROAD COMMISSION IMPROVED JORDAN LAKE ROAD IN 1965.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
AT A DEPTH OF 3" BELOW THE PAVED ROAD SURFACE AND OPPOSITE A OCCUPATION LINE EAST AND WEST FOUND A NAIL AND WASHER. BELOW NAIL AND AT A DEPTH OF 24" FOUND A 3/4" x 8" BOAT SPIKE NEXT TO A STONE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
REPLACED THE BOAT SPIKE WITH A 7/8" x 30" STEEL ROD WITH A 4" DIAMETER CAP STAMPED "IONIA COUNTY SURVEY MONUMENT- P.S. 25863" SET IN A MONUMENT BOX WITNESSED BY:

N&T	NORTH SIDE POWER POLE	EAST 37.35'
N&T	NORTH SIDE TWIN 12" ELM	S 60° W 33.32'
N&T	NORTH SIDE 5" ASH	N 50° W 33.82'
N&T	NORTHEAST SIDE TRIPLE 6" ASH	N 31° W 44.54'

CENTERLINE OF ROAD 1' WEST

Signed by Marinus A. Mulder Date 11-3-99

Surveyor's Michigan License No. 25863

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Ratified by Peer Group  
P.A. 345 Ionia County

Date August 18, 1999  
Marinus A. Mulder, Chairman

