

**SURVEY & REMONUMENTATION**

DEC 02 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **003** PAGE **361**

For corners in IONIA Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T6 N R7 W H-9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
IONIA COUNTY  
RECEIVED FOR RECORD

12 NOV 97 3:55 P.M.

DIANE W. ADAMS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on JUNE 11 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR JOHN MULLETT IN 1831. MULLETT CALLED FOR A 4" TAMARACK TREE FOR H-9 WITH NO WITNESSES.

PERPETUATION: THERE ARE NO RECORDED SURVEYS BY THE IONIA COUNTY SURVEYOR FOR H-9.

FORMER STATE HIGHWAY U.S. 16 CROSSES THIS CORNER IN AN EAST-WEST DIRECTION. THIS HIGHWAY WAS CONSTRUCTED IN 1928. THE MICHIGAN DEPARTMENT OF TRANSPORTATION DOES NOT HAVE WITNESS INFORMATION FOR H-9. THE IONIA COUNTY ROAD COMMISSION DOES NOT HAVE INFORMATION FOR H-9.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND P.K. NAIL AT ROAD SURFACE OPPOSITE FENCE LINE SOUTH. 2" BELOW P.K. NAIL FOUND REMAINS OF SPIKE AND WASHER, THE TYPE USED BY THE COUNTY ROAD COMMISSION. EXCAVATED BELOW SPIKE (5") TO ORIGINAL CONCRETE ROAD SURFACE BUT FOUND NO OTHER EVIDENCE. ACCEPTED NAIL AS THE BEST AVAILABLE EVIDENCE OF THE PERPETUATED CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET A 7/8" STEEL ROD WITH A 4" DIAMETER CAP STAMPED "IONIA COUNTY - 25863" IN PLACE OF THE NAIL WITNESSED BY:

- NAIL & TAG WEST SIDE 26" TRIPLE MAPLE S 10° E 51.75 FEET
- NAIL & TAG EAST SIDE 6" ELM S 8° W 35.42 FEET
- NAIL & TAG WEST SIDE 8" ELM N 30° E 40.31 FEET
- NAIL & TAG WEST SIDE 12" ELM NORTH 29.07 FEET

Ratified by Peer Group  
P.A. 645 Ionia County

Date 9-24-97

Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder

Date 10-3-97

Surveyor's Michigan License No. 25863

