

SURVEY & REMONUMENTATION

REMONUMENTATION CORNER

OCT 11 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

Ionia (County) Located In: Corner Code I-1

1. Public Land Survey	T <u>6N</u> R <u>7W</u>	<u>I-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
IONIA COUNTY
RECEIVED FOR RECORDS
94 JUN -6 P3:52
Dwayne M. Mulder
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on November 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, Lucious Lyon in 1826. Being the Southwest corner of Section 35, T7N-R7W. When U.S. Deputy Surveyor, John Mullett ran the section line North between Sections 2 & 3 T6N-R7W he intersected the township line at the standard corner. A wood post was set by Lyon witnessed by 6" Beech N 46° E 24 links and 12" Beech N 46° W 53 links. There is no recorded county survey information for this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Excavated old road bed and found a stone pile (3 large stones) 16" deep in line with a fence row running East & West. Accepted this as the corner and set a 3/4" steel bar in the center of the stone pile.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 3/4" x 24" steel bar with a 2 3/4" diameter cap stamped "P.L.S. 25863" in the center of a stone pile witnessed by:

- Nail & tag Northwest side 8" Elm N 48° E 27.48'
- Nail & tag Northeast side 10" Ash S 46° E 36.88'
- Nail & tag East side 4" x 4" wood sign post N 20° W 100.66'
- Nail & tag West side 10" Twin Elm S 9° E 47.02'
- Nail & tag top of 8" wood post S 56° W 32.96'

Ratified by Peer Group
P.A. 348 Ionia County

Date 4-20-94 m.g.m.
Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date June 6, 1994

Surveyor's Michigan License No. 25863