

**SURVEY & REMONUMENTATION**

OCT 11 1994

COMMISSION

REMONUMENTATION CORNER

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

or corners in

Tonia  
(County)

Located In:

Corner Code #

Public Land Survey

T 6N R 7W

I-2

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Miscellaneous

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
IONIA COUNTY  
RECEIVED FOR RECORD  
94 JUN -6 P 3:52  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Marinus Mulder, in a field survey on October 27, 1993,  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

This corner was first established by U.S. Deputy Surveyor, John Mullett in 1830. A wood post was set witnessed by 8" Beech S 11° E 29 links and a 11" Beech N 37° W 6 links.

There is no recorded county survey information for this corner.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Excavated road bed opposite old possession lines to the East & West and found a large stone pile 12" below old road surface. Accepted this as the position of I-2 and set a 3/4" steel bar in the center of the stone pile.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 3/4" x 24" steel bar with a 2 3/4" diameter cap stamped "P.L.S. 25863" in the center of a stone pile witnessed by:

- Nail & tag North side 6" Box Elder N 62° W 22.91'
- Nail & tag Southeast side 6" Walnut S 33° W 29.10'
- Nail & tag Northeast side 14" Twin Elm N 12° W 57.39'
- Nail & tag North side 8" Maple S 75° E 35.45'

Ratified by Peer Group  
P.A. 345 Ionia County

Date 4-20-94 M.A.M.  
Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder

Date June 6, 1994

Surveyor's Michigan License No. 25863