

**SURVEY & REMONUMENTATION**

OCT 07 1993

REMONUMENTATION CORNER

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia  
(County)

Located In:

Corner Code ##

- |                                    |             |             |             |
|------------------------------------|-------------|-------------|-------------|
| 1. Public Land Survey              | T <u>6N</u> | R <u>7W</u> | <u>I-10</u> |
|                                    | T _____     | R _____     | _____       |
|                                    | T _____     | R _____     | _____       |
|                                    | T _____     | R _____     | _____       |
| 2. Property Controlling in Section | S _____     | T _____     | R _____     |
|                                    | S _____     | T _____     | R _____     |
| 3. Miscellaneous Property in Sec.  | S _____     | T _____     | R _____     |
|                                    | S _____     | T _____     | R _____     |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

*John M. Davies*  
REGISTER OF DEEDS

93 SEP 21 P 3:21

STATE OF MICHIGAN  
IONIA COUNTY  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on June 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner first set by U.S. Deputy Surveyor John Mullett between August 1830 and April 1831. Set post witnessed by (1) 18" Elm S 48° W 6 links (2) 6" Black Ash N 28° E 16 links.

No record of perpetuation of corner by the County Surveyor. Prior to construction of Interstate I-96 the Ionia County Road Commission found this corner marked by a stone and set a 3/4" solid shaft with the following witnesses: Fence post S 42° E 37.39', telephone pole N 80° E 27.18', power pole N 87° W 96.40' circa 1956.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" shaft and stone on the South right of way fence of Highway I-96. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 3/4" x 30" steel shaft and replaced with a 3/4" x 36" steel rod with a 2 3/4" cap stating "Ionia County P.S. 25863" next to stone.

Witnesses:

- Nail & tag Southwest side 6" Ash S 60° E 36.91'
- Nail & tag Southwest side 16" Ash S 34° E 24.40'
- Nail & tag West side 3" Elm S 39° W 24.08'
- Nail & tag North side quad 10" Ash S 87° W 15.55'

This corner is at the base of the right of way fence for I-96

Signed by *marinus mulder*

Date August 30, 1993

Surveyor's Michigan License No. 25863

*filed 10/11/93*