

**SURVEY &
REMONUMENTATION
COMMISSION**
APR 10 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
IONIA
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 6N R 7W J-1
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
IONIA COUNTY
RECEIVED FOR RECORDS

94 DEC 29 P 1:58

David M. DeBora
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on APRIL 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
THIS CORNER WAS NOT SET BY U.S. GOVERNMENT SURVEYORS. THERE IS NO WRITTEN RECORD OF COUNTY SURVEYOR ESTABLISHMENT OF THIS CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
THE POSITION OF J-1 IS IN AN OLD TREE ROW INTERSECTION WITH NO STANDING FENCE EXISTING ALTHOUGH THERE IS BURIED REMAINS OF FENCE WIRE. THIS CLOSING CORNER WAS SET HALF-WAY BETWEEN THE NORTHEAST CORNER AND THE NORTHWEST CORNER OF SECTION 2, AND ON THE TOWNSHIP LINE. J-1 IS 2.40 FEET WEST OF THE SOUTH 1/4 CORNER OF SECTION 35, T7N-R7W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A 3/4" X 36" STEEL BAR WITH A 2 3/4" DIAMETER CAP STAMPED "P.L.S. 25863" WAS SET FOR THE POSITION OF THIS CORNER
WITNESSED BY:
NAIL & TAG SOUTH SIDE 14" TWIN POPLAR S 85° W 15.41'
NAIL & TAG NORTHWEST SIDE 8" POPLAR S 62° E 2.15'
NAIL & TAG NORTH SIDE 24" POPLAR CLUMP N 83° E 6.06'
NAIL & TAG WEST SIDE 40" POLAR CLUMP EAST 38.09'
SOUTH 1/4 CORNER SECTION 35, T7N-R7W EAST 2.40' EAST (3/4" X 36" STEEL ROD WITH A 2 3/4" DIAMETER CAP STAMPED P.L.S. 25863)

Ratified by Peer Group
P.A. 345 Ionia County

Date 4-20-94
Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date 12-27-94
Surveyor's Michigan License No. 25863