

**SURVEY & REMONUMENTATION**

OCT 1 1 1994

COMMISSION

REMONUMENTATION CORNER  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

— Ionia — (County) Located In: Corner Code =#

1. Public Land Survey	T	6N	R	7W	K-2
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

STATE OF MICHIGAN  
 IONIA COUNTY  
 RECEIVED FOR RECORDS  
 94 JUN -6 P 3:53  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first established by U.S. Deputy Surveyor, John Mullett in 1830. A wood post was set witnessed by a 8" beech N 55° W 11 links and a 7" beech S 58° E 29 links.  
 There are no recorded county surveys or notes for this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Excavated gravel road bed opposite 1/4 fence line to the East and found large stone. Accepted stone as the corner and set a 3/4" x 24" steel bar next to the stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 24" steel bar with a 2 3/4" diameter cap stamped "P.S. 25863"  
 Witnessed by:  
 Nail & tag Northwest side 22" maple N 48° E 34.68'  
 Nail & tag East side 16" pignut hickory N 35° W 31.22'  
 Nail & tag Southeast side 20" maple S 44° W 37.74'  
 Nail & tag North side 18" maple S 37° E 41.41'

Ratified by Peer Group  
 P.A. 345 Ionia County

Date 4-20-94 M.A.M.  
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date 4-21-94  
 Surveyor's Michigan License No. 25863