

**SURVEY &  
REMONUMENTATION**

DEC 1 6 1996

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **3** PAGE **266**

**COMMISSION**

For corners in

<u>IONIA</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>6</u> N R <u>7</u> W	<u>K-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
IONIA COUNTY  
RECEIVED FOR RECORD

24 OCT 96 3:56 P.M.

DIANE M. ADAMS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on JULY 3 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR, JOHN MULLETT IN 1831. A WOOD POST WAS SET WITNESSED BY A: 14" ELM S 80° E 31 LINKS AND A 6" LYNN N 75° W 7 LINKS.  
THERE IS NO RECORDED COUNTY SURVEY INFORMATION FOR K-4.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO MODERN DAY MONUMENTATION WAS FOUND AT THIS LOCATION. OPPOSITE FENCE LINES EAST AND WEST EXCAVATED GRAVEL ROAD (HARWOOD ROAD) WITH A BACKHOE AND FOUND A NICE SYMETRICAL STONE PILE WITH A POINTED STONE AND LARGE FLAT STONE ON EDGE ABOUT 12" BELOW THE SURFACE. ACCEPTED THIS STONE PILE AS THE PERPETUATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A 7/8" X 24" STEEL BAR WITH A 2 3/4" CAP IN THE CENTER OF THE STONE PILE. THE CAP IS STAMPED "IONIA COUNTY-25863" WITNESSED BY:  
NAIL & TAG SOUTH SIDE 22" ELM N 89° W 39.96'  
NAIL & TAG 8" ASH N 75° E 25.46'  
TOP CENTERLINE 2" STEEL POST S 83° E 26.82'  
NAIL & TAG NORTHWEST SIDE 3" ELM N 46° E 35.15'



Ratified by Peer Group  
P.A. 345 Ionia County

Date 9-26-96  
Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date OCTOBER 22, 1996

Surveyor's Michigan License No. 25863