

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 3 PAGE 268

For corners in IONIA
(County)

Located In: Corner Code #

- 1. Public Land Survey T6 N R7 W K-6
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

STATE OF MICHIGAN
IONIA COUNTY
RECEIVED FOR RECORD

24 OCT 96 3:57 P.M.

DIANE M. ADAMS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on JULY 3 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR JOHN MULLETT IN 1831. A WOOD POST WAS SET WITNESSED BY A: 8" BEECH N 62° E 9 LINKS AND A 14" ELM S 29° W 24 LINKS. THERE IS NO RECORDED COUNTY SURVEY INFORMATION FOR K-6.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO MODERN DAY MONUMENTATION WAS FOUND FOR K-6. EXCAVATED GRAVEL ROAD OPPOSITE A FENCE LINE RUNNING WEST WITH A BACKHQE. 12" BELOW THE ROAD SURFACE (HARWOOD ROAD) FOUND A LARGE STONE PILE. ACCEPTED THE PILE OF STONES AS THE PERPETUATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A 7/8" X 24" STEEL BAR WITH A 2 3/4" DIAMETER CAP STAMPED "IONIA COUNTY-25863" SET IN CENTER OF THE STONE PILE.

WITNESSED BY:

- NAIL & TAG EAST SIDE FENCE POST S 31° W 59.23 FEET
- NAIL & TAG SOUTHEAST SIDE 6"X6" WOOD POST S 72° W 29.81 FEET
- NAIL & TAG NORTH SIDE 6"X6" WOOD POST S 87° W 28.22 FEET
- WEST EDGE 8" ANGLE IRON POST (2' ABOVE GROUND) S 76° E 25.15 FEET



Ratified by Peer Group
P.A. 343 Ionia County

Date 9-26-96

Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder

Date OCTOBER 22, 1996

Surveyor's Michigan License No. 25863