

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in IONIA Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 6 N R 8 W E-1
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

16 NOV 95 4:21 P.M.

DIANE N. ADAMS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on JULY 18, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR, JOHN MULLETT IN 1830. A WOOD POST WAS SET 35 LINKS WEST OF THE STANDARD CORNER WITNESSED BY A 12" WHITE OAK S 43° E 52 LINKS AND A 12" WHITE OAK S 89° W 52 LINKS.
 PERPETUATION: THOMAS CORNELL FORMER IONIA COUNTY SURVEYOR PERFORMED A SURVEY OF SECTION 4, OCTOBER OF 1877. CORNELL DID NOT SAY WHAT HE SET FOR E-1 BUT GAVE 2 WITNESSES BEING A 12" WHITE OAK S 43° E 52 LINKS AND A 12" WHITE OAK S 89° W 52 LINKS BEING THE SAME WITNESSES AS THE G.L.O. D.C. CRAWFORD FORMER IONIA COUNTY SURVEYOR IN A MARGINAL NOTE ON PAGE 531 OF THE COUNTY SURVEYORS COPY OF THE G.L.O. NOTES STATED HE ESTABLISHED E-1 FROM OLD LAND MARKS BUT GAVE NO WITNESSES. THIS WAS DATED 1888. PROFESSIONAL SURVEYOR FRANCIS SPICER NO. 7877 RECORDED E-1, AUGUST 20, 1972 FOUND IN LIBER 1 PAGE 44. SPICER SET A T IRON IN THE CENTERLINE OF THE GRAVEL ROAD OPPOSITE A FENCE LINE SOUTH AND AT A DISTANCE OF 23.1 FEET FROM THE CENTERLINE OF A ROAD TO THE NORTH.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND A T IRON CLOSE TO (WITHIN 0.20 FEET) A LARGE STONE IN STONE PILE 10" DEEP. ALSO FOUND 1" X 11" POINTED SHAFT IN THE STONE PILE. ACCEPTED THE 1" X 11" SHAFT AND THE STONE AS THE PERPETUATED CORNER.

Ratified by Peer Group
 P.A. 345 Ionia County

Date Nov. 1, 1995
 Marinus A. Mulder, Chairman

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET A 3/4" X 24" STEEL ROD WITH A 2 3/4" DIAMETER CAP STAMPED "IONIA COUNTY P.S. 25863" IN PLACE OF THE 1" X 11" SHAFT - NEXT TO THE LARGE STONE WITNESSED BY:
 NAIL & TAG NORTH SIDE 26" HICKORY S 41° W 30.48 FEET
 NAIL & TAG NORTH SIDE 30" MAPLE S 61° W 49.63 FEET
 NAIL & TAG WEST SIDE 25" OAK N 32° E 90.44 FEET
 NAIL & TAG NORTHWEST SIDE POWER POLE N 56° E 76.04 FEET
 SOUTHWEST CORNER OF SECTION 33, T7N-R8W (3/4" ROD WITH 2 3/4" DIAMETER CAP) EAST 23.58 FEET

Signed by Marinus A. Mulder Date 11-14-95

Surveyor's Michigan License No. 25863