

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 003 PAGE 196

For corners in
IONIA
 (County)

Located In: Corner Code #

1. Public Land Survey T 6N R 8W F-8
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

10 OCT 95 4:05 P.M.

DIANE M. ADAMS
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

I, MARINUS MULDER, in a field survey on March 16 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

The center of section was not set by U.S. Government Surveyors. Establishment: A.C. Smith former Ionia County Surveyor, performed a sectional survey of Section 21, T6N-R8W, October 27, 28 and 29 of 1875, recorded in Volume 1 page 142 of the Ionia County Surveyors Records. Smith intersected the 1/4 lines and showed 1 witness being a 16" White Oak N 71° E 45 links. He did not say what he set. Professional Surveyor, Paul VanKooten No. 08618 in March, 1980 recorded a survey of a portion of Section 21, found in Liber 450, page 831 of County records. VanKooten shows a pointed stone for F-8 with 2 witness objects.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found pointed cut stone in the occupied North-South and East-West 1/4 line fences. No standing fence remains to the South or West, but traces remain. Smith's 1875 witness tree is gone. VanKooten's 2 witness tree's still remain. Accepted the stone as the position of F-8.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set a 3/4" x 36" steel rod with a 2 3/4" diameter cap stamped "Ionia County P.S. 25863" on the Southeast side of the stone witnessed by:

- Nail & tag East side 26" Oak N 20° W 5.79 feet
- Nail & tag East side 28" Oak S 20° W 3.98 feet
- Nail & tag Southeast side 20" Oak N 40° E 13.03 feet
- Nail & tag North side 22" Cherry S 81° E 28.67 feet

Ratified by Peer Group
 P.A. 345 Ionia County

Date 9-27-95
 Marinus A. Mulder, Chairman

Signed by marinus a. mulder Date OCTOBER 2, 1995

Surveyor's Michigan License No. 25863