

SURVEY & REMONUMENTATION COMMISSION

APR 10 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

IONIA
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 6N R 8W F-13
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, MARINUS MULDER, in a field survey on SEPTEMBER 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR JOHN MULLETT IN 1830. A WOOD POST WAS SET WITNESSED BY A 6" IRON WOOD N 36 1/2° E 15 LINKS AND A 7" ELM N 73° W 11 LINKS.
 THERE IS NO RECORD OF COUNTY SURVEYOR PERPETUATION OF THIS CORNER. THE IONIA COUNTY ROAD COMMISSION SHOWS WITNESSES TO F-13 IN THEIR CORNER INDEX MAP. THEY CALL FOR A POINTED STONE 1.5 FEET EAST OF A FENCE RUNNING NORTH AND 2.0 FEET SOUTH OF A FENCE RUNNING EAST AND WEST. RANDAL VUGTEVEEN PROFESSIONAL SURVEYOR NO. 21272 RECORDED F-13 MARCH 1993 FOUND IN LIBER 3 PAGE 10 OF ACT 74 RECORDS. VUGTEVEEN FOUND A POINTED STONE AT THE INTERSECTION OF FENCE LINES AND PUT A "X" ON TOP OF STONE AND TOOK 6 WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 6" X 9" X 6" HIGH STONE WITH A "X" CHISELED ON THE TOP. AT THE FENCE LINE INTERSECTION AS CALLED FOR. ACCEPTED STONE AS THE CORNER. DID NOT SET A STEEL MARKER NEXT TO STONE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 LEFT 6" X 9" X 6" HIGH STONE AS THE MONUMENT FOR F-13.

- WITNESSED BY:
- NAIL & TAG SOUTH SIDE 28" OAK EAST 8.75'
 - NAIL & TAG NORTHWEST SIDE 26" OAK N 76° E 11.11'
 - NAIL & TAG WEST SIDE 22" HICKORY N 15° W 37.10'
 - NAIL & TAG EAST SIDE 12" OAK S 30° W 12.09'
 - NAIL & TAG NORTHWEST SIDE 9" MAPLE S 50° W 28.56'

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 94 REC 29 P 2:01
 D. J. Mulder
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**Ratified by Peer Group
 P.A. 345 Ionia County**

Date 12-22-94
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date 12-27-94

Surveyor's Michigan License No. 25863