

RECEIVED

JAN 13 2000

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 4 PAGE 85

For corners in SECTION IONIA (County)

Located In:	Corner Code #
T6 N R8 W	G-11
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.
- 4. Lot No. , Recorded Plat
- 5. Private Claims

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 23 NOV 99 2:58 P.M.
 DIANE M. ADAKS
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on JULY 15 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR JOHN MULLETT IN 1830. A WOOD POST WAS SET WITNESSED BY A: 12" BEECH S 28° E 19 LINKS AND A 14" WHITE OAK N 12° E 28 LINKS.

PERPETUATION: A.C. SMITH FORMER IONIA COUNTY SURVEYOR PERFORMED A SURVEY OF SECTION 34, DECEMBER 3 AND 4, 1875 RECORDED IN VOLUME 1, PAGE 154 OF IONIA COUNTY SURVEY RECORDS. SMITH RECORDED THAT HE SET A STAKE BY GOVERNMENT BEARING TREES.

THE IONIA COUNTY ROAD COMMISSION HAS WITNESSES FOR G-11 FOUND IN THE SECTION CORNER INDEX SHEETS. A 1/2" PIPE IS CALLED FOR WITNESSED BY: 30" MAPLE N 52° W 39.88 FEET; 10" ELM S 10° E 118.85 FEET; 16" ELM S 15° W 64.80 FEET.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 AT THE INTERSECTION OF PORTLAND ROAD AND MICK ROAD AND AT A DEPTH OF 6" BELOW THE GRAVEL SURFACE, FOUND A 1/2" x 15" PIPE. EXCAVATED TO A DEPTH OF 40" AND FOUND A STONE BELOW THE PIPE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 REPLACED THE 1/2" PIPE WITH A 3/4" x 36" STEEL ROD WITH A 2 3/4" DIAMETER CAP STAMPED "IONIA COUNTY SURVEY MONUMENT - P.S. 25863"
 WITNESSED BY:

- N&T SOUTHEAST SIDE WOOD CORNER POST N 39° E 40.88 FEET
- N&T WEST SIDE WOOD POST S 16° E 51.29 FEET
- N&T FENCE POST S 30° E 40.10 FEET
- WEST EDGE WEST LEG ROAD SIGN POST NORTH 18.02 FEET

Signed by Marinus A. Mulder Date 11-3-99

Surveyor's Michigan License No. 25863

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1983

Ratified by Peer Group
 P.A. 345 Ionia County

Date August 18, 1999
 Marinus A. Mulder, Chairman

