

SURVEY & REMONUMENTATION

OCT 07 1993

COMMISSION

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia (County) Located In: Corner Code #

- 1. Public Land Survey T 7N R 5W D-1
- 2. Property Controlling in Section S ___ T ___ R ___
- 3. Miscellaneous Property in Sec. S ___ T ___ R ___
- 4. Lot No., _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 93 SEP 21 P 3:26
 Dianne M. Adams
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on July 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 U.S. Deputy Surveyor, Orange Risdon, subdivided Lyons Township May 18th to July 30th of 1831. This 1/4 closing corner was not set by the Government Surveyors.
 Establishment: D.C. Crawford former Ionia County Surveyor set this corner in 1891. Whose witnesses are found as marginal notes on a copy of the County Surveyors G.L.O. notes. He stated (1) 6" Hickory N 64° 30' E 74 links (2) 12" White Oak S 26°30' W 35.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Present to witness the potential finding of this corner were the following: Dianne Adams, Ionia County Register of Deeds, Mary Cusack, Ionia County Commissioner, Russel Gregory, Ionia County Historian and editor of the Ionia Sentinel Newspaper and Survey Assistant, J.B. Bigelow. Crawford's witnesses of 1891 still remain, one being a stump. J.B. Bigelow and I pulled witness distance and excavated road bed with a hammer drill and found 2 1/4" solid glazed tile with stones at base about 12" below gravel road surface of Nickleplate Road. Set a 3/4" x 24" steel rod next to cylinder and accepted as a careful and faithful perpetuation of the Government Corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 3/4" x 24" steel rod with a 2 3/4" cap stating "Ionia County P.S. 25863" with the following witnesses:
 Nail & tag North side 16" Hickory N 70° E 49.61'
 Nail & tag East side 6" x 6" post S 02° W 30.04'
 Nail & tag Northeast side 38" Oak Stump S 35° W 24.10'
 Nail & tag South side 18" Willow N 55° W 47.29'

Signed by Marinus Mulder Date August 30, 1993
 Surveyor's Michigan License No. 25863

filed 10/11/93