

1993

COMMISSION

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia (County) Located In: Corner Code ##

1. Public Land Survey T 7N R 5W E-1

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

REGISTER OF DEEDS

93 SEP 21 P 3:23

STATE OF MICHIGAN IONIA COUNTY RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marinus Mulder, in a field survey on June 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
U. S. Deputy Surveyor, Orange Risdon, set this closing corner May 18th to July 30th of 1831. Set post witnessed by: (1) 18" White Oak S 61° E 55 links (2) 12" Black Oak S 37° W 72 links
Perpetuation: D.C. Crawford former Ionia County Surveyor perpetuated this corner in 1891, whose witnesses are found as marginal notes on a copy of the County Surveyors G.L.O. notes. He stated: (1) 6" Hickory N 32 1/2" E 58 1/2 links (2) 8" White Oak S 57° W 78 links
James Porter P.S. # 19003 found on March 14, 1977, Crawford's clay cylinder of 1891 and set a railroad spike next to it. Recorded in Liber 1 page 206.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found railroad spike and clay cylinder and accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Removed spike and set a 3/4" x 24" steel bar with a 2 3/4" cap stating "Ionia County P.S. 25863" with the following witnesses:
Nail & tag West side 26" Oak S 64° W 52.25'
Nail & tag West side 12" Oak N 49° E 44.30'
Nail & tag South side 16" Hickory S 60° E 63.94'
Nail & tag East side 24" Hickory N 55° W 65.68'

Signed by Marinus Mulder Date August 30, 1993
Surveyor's Michigan License No. 25863