

**SURVEY & REMONUMENTATION**

REMONUMENTATION CORNER

OCT 11 1994

**LAND CORNER RECORDATION CERTIFICATE**  
**COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ionia  
(County)

Located In:

Corner Code ##

- |                                    |                         |             |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey              | T <u>7N</u> R <u>5W</u> | <u>E-11</u> |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |

*Oliver M. DeWitt*  
 REGISTER OF DEEDS

94 JUN -6 P 3:55

STATE OF MICHIGAN  
 IONIA COUNTY  
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on October 6, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first established by U.S. Deputy Surveyor, Orange Risdon in 1831. A wood post was set witnessed by a 10" White Oak S 52° W 80 links and a 10" White Oak N 37° E 85 links.

Continued on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

It is known that County Surveyor, Crawford set many clay cylinders for Government Corners. Found 2 1/4" solid clay cylinder with a boat spike next to it. Accepted as the corner. Removed boat spike and set a 3/4" steel bar and cap next to clay cylinder.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 24" steel bar with a 2 3/4" diameter cap stamped "P.S. 25863" next to a 2 1/4" clay cylinder  
 Witnessed by:

- Nail & tag Northeast side 20" Hackberry S 52° E 52.41'
- Nail & tag Southeast side 18" Cedar N 12° E 23.33'
- Nail & tag Southwest side wood post N 37° E 34.19'
- Nail & tag East side 6" Oak S 25° W 23.90'

Ratified by Peer Group  
 P.A. 345 Ionia County

Date 4-20-94 M.A.M.  
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date April 20, 1994  
 Surveyor's Michigan License No. 25863

Continued from A:

D.C. Crawford former Ionia County Surveyor performed a sectional survey of Section 33 and 34 of T7N-R5W April 18 & 19 of 1883, which is found in Volume 1 page 302 of the Ionia County Surveyors Records. Crawford shows no witnesses or does not state what he set. Crawford has marginal witness notes for E-11 found in the County Surveyors copy of the G.L.O. notes (page 115). He states 1891, 8" Burr Oak N 40° W 64 1/2 links and 3" Sugar S 53° E 68 1/4 links. The Ionia County Road Commission has witnesses to this corner on their index maps as follows: 1959: 2" Vitrified clay cylinder and iron; 6" Cedar Northeast 22.95', power pole Northeast 119.10', 18" Maple Southeast 45.40' (Crawford's witness of 1891).

This corner was recorded by Professional Surveyor, James Porter no. 19003 found in Ionia County Public Act 74 recordation file Liber 1 page 181, July 16, 1976. Porter states that he found a boat spike alongside a vitrified clay monument as found by the Ionia County Road Commission and used by Consumers Power Company in a survey dated 11-19-42. Porter took 3 witnesses.